



- PIER LEGEND**
- = SUPPORT UNDER WAITING OPENINGS
 - = SUPPORT AT WAITING COLUMN
 - = SUPPORT UNDER WAITING WALL
 - = PIER PORCH/RECESSED ENTRY

- SERVICE DROP LEGEND**
- = ELECTRICAL DROP
 - = WATER INLET
 - = DWV PLUMBING DROP
 - = GAS INLET

20 lb ROOF LOAD SIDEWALL OPENING PIER LOAD 18" BOX WIDTH	SIDEWALL OPENING (FT)					
	3	4	5	6	8	10
REQUIRED PIER LOAD (LBS)	1306	1488	1669	1850	2213	2575

*FOR 30 lb & 40 lb ROOF LOAD REFER TO TABLES 7 & 7a IN THE INSTALLATION MANUAL.

- NOTES:**
- REFER TO TABLES 6 AND 6a IN THE INSTALLATION MANUAL FOR LOAD ON FRAME PIER FOOTINGS FOR HOMES THAT DO NOT REQUIRE PERIMETER BLOCKING. REFER TO TABLES 7 AND 7a IN THE INSTALLATION MANUAL FOR LOAD ON FRAME PIER FOOTINGS FOR HOMES THAT REQUIRE PERIMETER BLOCKING. REFER TO TABLES 10 AND 10a TO DETERMINE FOOTING SIZE FOR ALL PIERS.
 - REFER TO TABLE 9 FOR PIER CONFIGURATION AND MAXIMUM ALLOWABLE HEIGHTS. CROSS REFERENCE THE PIER HEIGHT WITH THE MAXIMUM ALLOWABLE FLOOR HEIGHT LISTED IN THE FRAME TIEDOWN CHARTS (TABLE 18, 19, AND 20).
 - THE MAXIMUM SPACING FOR 8" I-BEAMS IS 8 FEET, 10" & 12" I-BEAMS IS 10 FEET.
 - SERVICE DROP LOCATIONS IDENTIFIED ARE APPROXIMATE.
 - FLOOR WIDTH SHOWN IS FOR STANDARD PRODUCT ONLY. CONTACT THE MFG FACILITY FOR SPECIFICATIONS OF OPTIONS ORDERED.

1,260 SQ.FT. (STD PLAN "CONDITIONED")
N/A SQ.FT. (W/OPT. PORCH/RECESS "CONDITIONED")

Product Designers: Alex Whaley

CMH
MANUFACTURING

Model #: Y5316723C Drawing #: 355224
Date: 1/26/13 Scale: N.T.S.

18' x 72' Yes The Boss

FRAME PIERS

2 **ABUSIXION** BCR-227127
8.1.16 AGW